

**PRASAR BHARATI
INDIA'S PUBLIC SERVICE BROADCASTER
ALL INDIA RADIO, SRINAGAR**

No. SGR-1(2)(5)/2019-20/ES

Dated: 21-01-2020

M/s _____


Subject: - Quotations for petty works at HPT Narbal and HPT Pampore under All India Radio, Srinagar

Dear Sir,

All India Radio, Srinagar invites sealed quotations for petty works at HPT Narbal and HPT Pampore under All India Radio, Srinagar. The works are required to be undertaken as per Annexure. The quotation shall be sent in sealed envelope conforming to following terms and condition:-

1. The cover shall be super-scribed with the following details:-
 - a) The work for which the tenders are enclosed
 - b) Opening date of quotation
 - c) Reference No. of the enquiry letter
2. The sealed quotations shall reach to this office on or before 12/02/2020 up to 03 pm at the address given below:-

The Assistant Engineer (Stores)
All India Radio,
Srinagar-190001.
3. The quotations will be opened on same day at 3 pm in presence of those tenderers or their authorised agents whom may choose to attend.
4. The Quotation/Tender Box is available at the main Gate of the Station.
5. The quotation received without proper seal and prescribed details on the cover will be out rightly rejected. Changes in the quote/tender after opening of quotations will not be admissible.
6. GST Registration certificate of the firm shall be enclosed.
7. Payment: - Full payment will be released by the office after satisfactory completion of work. No advance payment will be made.
8. Validity: Quotation shall remain valid for a period of six months from the date of its opening.
9. Work offered should strictly comply with the scope of work/specification as per the Annexure.
10. Item wise rates or per unit rates wherever is specified for these works shall be quoted by the tenderers. GST amount along with the rate in percentage shall be indicated for each of the items/jobs.
11. This office reserves the right to accept or reject any of the quotations without assigning any reason.


Assistant Engineer (Stores)

For Dy. Director General/Head of Office

ANNEXURE


After the issue of work order, the contractor has to carry out following works at HPT Narbal (Part A of the Annexure) and HPT Pampore (Part B of the Annexure):-

PART-A (HPT-Narbal)

1. Providing and fitting(p/f) of 12 mm board on walls for making the frame for panelling in Engineers Room having size of:- Height 10 ft x Width 13.5 ft x Length 17ft. (door 7'x5'-1 No ; windows 3'x4'-3nos; ventilator 1.5' x3'-3 Nos).
2. Providing and fitting of wooden paneling (of Budloo wood) and polishing on it.
3. Providing and fitting of woollen curtains of superior quality at the doors and windows. Per meter rate shall be quoted.
4. Providing and fitting of 12 mm board on false ceiling of the room for making the frame for laminated board 6 mm and then p/f of laminated board 6mm having size:-13.5 ft x 17 ft.
5. Dismantling of old wooden door with frame from the same room and p/f of new aluminum door with frame and glass pans as per the requirement having size:-5ftx7ft.
6. P/F of electrical accessories i.e., led fitting 12/15 watt on ceiling, switch plate with switches for on/off, sockets 3 pin/ 2pin, 15 amp, 5 amp, wire for lighting system, heating system etc. as per requirement in the same room.
7. Repairing of aluminum door of entrance of Transmitter hall.
8. P/F of aluminum door with frame for Diesel Section entrance having size:-3ft x 7ft and fixing of the laminated sheet of remaining space upper side of the door.

PART -----B (HPT-Pampore)

1. Supply and Installation of water tank of 2000 liters with water pipe lines $\frac{3}{4}$ inch x 20 ft- 10 Nos along with other accessories i.e. elbow, socket, nipple, union, reducer etc.
2. Digging of holes depth 36" x width 12" and filling with the cement & bajri and then fixing of 3" dia pipe of 4' in cement concrete work i.e. 3' underground and 1' upper ground remaining of 14' put in open area of total height of pipe 18ft. Only 18ftx3 inch dia pipes will be provided by this office. Rest of the items will be arranged by the contractor.
3. Supported with angle iron and joint with angle iron in pipes with welding works, providing and fitting of iron sheet 5ft x5ft-1 no and fixing on the top with welding work. Angle irons will be provided by the office.
4. Enamel Painting of two coats along with the primer and then painting with oil paint in two coats in pipes, angle irons and iron plates.


21/11/2020