



P R A S A R B H A R A T I
(INDIA'S PUBLIC SERVICE BROADCASTER)
CIVIL CONSTRUCTION WING, ALL INDIA RADIO
MUMBAI-91

No. AEC-I/BOV/12(NIQ)/2023-24/ 169

Dated: 13.11.2023

NOTICE INVITING QUOTATION

Sealed item rate quotations are invited by The Assistant Engineer (Civil)-I, CCW, AIR, Borivali, Mumbai-91 from the eligible and approved contractors of C.P.W.D. and those on appropriate list of B.S.N.L./M.T.N.L., M.E.S., State P.W.D. of Maharashtra and railways as well as eligible working contractor of CCW AIR for the following work, upto **15.00 hrs.** On **17.11.2023** which shall be opened on the same day at **15.30 Hrs.**

Blank quotation duly signed by Assistant Engineer shall be issued to the agency on submission of application with definite proof of having executed civil work and GST registration no. and acknowledgement of upto date GSTR 1 returns. The blank quotation verified and issued by Assistant Engineer shall only be validated and accepted authority.

Name of work : Providing aluminium glazed sliding widow to B, C type staff quarter of All India Radio, Nasik.					
Sr. No	Description	Qty.	Unit	Rate	Amount
----- AS PER ATTACHED SHEET -----					
TOTAL:					

CONDITIONS:

10. The work shall be carried out as per CPWD Specifications, 2009 Vol. I & II with upto-date correction slips and as per direction of Engineer-in-charge;
11. Time limit for completion of work is 15 (fifteen) days
12. Quoted rates shall be inclusive of all taxes and levies payable under the respective states including GST, nothing extra will be paid on any account;
13. The agency shall visit the site of work before quoting, as no extra payment will be made on any account. Such as extra thickness of base course depths and all height of buildings etc.
14. All type of security measures / precautions of labour shall be responsibility of agency during execution of work. No extra payment will be made on any account.
15. If the work is prolonged beyond stipulated time the penalty shall be imposed @ week.
16. The agency will be responsible for any defect for a period of 12 (twelve) months after issuing completion certificate for the work by Engineer-in-charge & client department. If any defect found during the defect liability period, the agency shall rectify the same within 7 days after receiving the notice from Engineer-in-charge in any form failing which the defective work shall be got rectified / replaced completely at the risk & cost of the agency and no claim whatsoever shall be entertained in this regards. The agency may note that the recovery shall be made from any of the payments due with the department or will be under legal obligation to refund the cost incurred by department in rectification / replacement of the defective work come to the notice of Engineer-in-charge during defect liability period;
17. No advance payment shall be made;
18. Labour should be above 18 years of age.

(M.G.Kurhe)

ASSISTANT ENGINEER (CIVIL)-I
CCW AIR PB (IPSB) MUMBAI-91

CONTRACTOR

Copy to:

5. The Executive Engineer (Civil), Civil Construction Wing, All India Radio, Mumbai-20;
6. The Assistant Engineer Civil (P), CCW, AIR, Mumbai.
7. Notice Board
8. Contractors M/s. _____

SCHEDULE OF WORK

Division
Sub-Division

State
Branch

Name of Work : Providing aluminium glazed sliding widow to B, C type staff quarter of All India Radio, Nasik.

ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
1	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead :					
1.1	Of area 3 sq. metres and below	14	each			SR
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :					
2.1	For fixed portion					SR
2.1.1	Powder coated aluminium (minimum thickness of powder coating 50 micron)	45	kg			
2.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)					
2.2.1	Powder coated aluminium (minimum thickness of powder coating 50 micron)	45	kg			SR
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):					

ITEM N ^o	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)	
3.1	With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	6	sqm				SR
4	Providing and fixing S.S. fly/ mosquito proof net to aluminium sliding window shutter including necessary screws etc complete as per direction of Engineer-in-charge.	3	sqm				MR
5	Providing and fixing concealed lock bronze anodising of required colour or shade to aluminium window shutters with necessary screws etc complete as per direction of Engineer-in-charge.	21	each				MR
6	Providing and fixing PVC roller of approved quality and make to aluminium window shutters with necessary screws etc complete as per direction of Engineer-in-charge.	42	each				MR
	Total						

Junior Engineer

Assistant Engineer

Executive Engineer


(M.G. KURHE)
ASSISTANT ENGINEER (CIVIL)-I
CCW, ALL INDIA RADIO MUMBAI-91