



प्रसारभारती / PRASAR BHARATI  
भारतीयलोकसेवाप्रसारक/ INDIA'S PUBLIC SERVICE BROADCASTER  
अपरमहानिदेशक(अभि.) (द.क्षे) कार्यालय/ O/o. ADDL. DIRECTOR GENERAL (E)(SZ)  
आकाशवाणी एवं दूरदर्शन / ALL INDIA RADIO & DOORDARSHAN  
स्वामीशिवानंदासालै, चेन्नई / SWAMY SIVANANDA SALAI, CHENNAI – 600 005

No. ADG(E)(SZ)/AIR/INST/IO - /2022-23/P

Date: 28.9.2022

To,

Sir,

**SUB:- SITC of False ceiling at 7 LPTV Stations at Devarkonda, Sirpur, Kayakulam, Pathanamthitta, Bidar, Bagalkot, and KGF.**

Sir,

Sealed quotations are invited for the following mentioned works at **6 LPTV Stations at Devarkonda, Sirpur, Kayakulam, Bidar, Bagalkot, and KGF in Kerala and Karnataka.**

S NO.	Description of work	Quantity	Unit Rate	Total Amount
1	Removal of existing old False ceiling system at 6 LPTV Stations.	<b>7 Jobs</b>		
2	SITC of new False ceiling system as per specification in Annexure -I at 6 LPTV Stations. 1.Devarkonda(Kerala) 2.Sirpur 3.Bidar(Karnataka) 4.Bagalkot(Karnataka) 5.KGF(Karnataka) 6 Kayamkulam(Kerala) 7 Pathanamthitta  Note: 1.Payment will be made as per actuals. 2.False ceiling Tiles has to be of M/s RAMCO make and model No should be pre	1)150 Sq.ft 2) 150 Sq.ft 3) 150 Sq.ft 4) 150 Sq.ft 5) 150 Sq.ft 6) 270 Sq.ft 7) 250 Sq ft		

	<p>Note: 1.Payment will be made as per actuals.</p> <p>2.False ceiling Tiles has to be of M/s RAMCO make and model No should be pre approved.</p> <p>3. Recession Light fittings of size 600X600 will be supplied by Department.</p>			
			<b>TOTAL</b>	
			<b>GST</b>	
			<b>GRAND TOTAL</b>	

**1)Consignee:**

1. Shri. Ranganadha Rangarajan,EA,Mobile.NO:9849669896. LPTV/100 W FM AIR, Devarkonda, Telengana,PIN 508248
2. Shri. Ch. Ravi, Technician Mob. 94410 20362, LPTV/100W FM AIR, Railway Station Road, Sirpur Khagaz Nagar, Telengana ,PIN 504296
3. Shri. Soma Technician, Mob. 8123199221, LPTV/100W FM AIR, Janavada Road, Bidar , Karnataka ,PIN 585401
4. Shri. M Somasekharaiah Sr. Technician, Mob. 9980790060, LPTV/ 100 W FM AIR, B T DA Compound, Vidyagiri, Kaladagi Road, Bagalkot, Karnataka PIN 587102
5. Shri. Sankarappa, Sr. Technician, Mob.9739316160, LPTV/100W FM AIR, Oorgaum, Kolar Gold Fields, Karnataka PIN 563120
6. Shri. Anilkumar A R, Technician, Mob . 94479 76320, LPTV/100 W FM AIR, Chirakadavam, Kayamkulam , Kerala PIN 690502
7. Shri. Venugopalan Nair, SEA, Mob. 94473 69292, LPTV/100 W FM AIR, Mannarmala, Pathanamthitta , Kerala PIN 689645

**2) Delivery Period :** Work should be completed within 60 days from the date of Work Order.

**3) Payment terms :** 100% of will be paid on satisfactory completion of the work.

**4) Eligibility Crieteria :** Firm should have carried out similar work in Govt departments in the past 3 years. Certificate in this regard be enclosed.

**5) Eligible Bidders** may send their Bids to Director(E), Room No 207, O/o Additional Director General(E), AIR & TV, Swamy Sivananda Salai, Chennai – 600005 on or before 2

PM on 14.10.2022. Bids will be opened at 2:30 PM on 14.10.2022. Bids should be marked on the Cover ' SITC Of False ceiling System at ~~4~~ LPTV stations'

**6) General terms and conditions:**

i) The bidder shall carry out the works with utmost care, not to damage any existing equipment. Bidder will be held responsible for any damages caused to property of AIR during the execution of the work and shall make good such damages at his own cost.


ii) All the safety precautions are to be ensured and safety tools/equipment are to be brought by the contractor.

iii) The contractor is liable to compensate the department for any damages to All India Radio property or personnel during the execution of work.

iv) This office does not take any responsibility for any mishap which may occur to him or any of his personnel/equipment during the course of work.

v) The undersigned has the right to accept or reject the quotation /quotations without assigning any reason.

6) The quotation should be valid for a period of 6 months from the date of opening them.



Yours faithfully

**K P sanjeev**

**Director (E)**

**Specification for snap grid false ceiling at 7 LPTV Stations at Devarkonda, Sirpur,  
Bidar, Bagalkot, KGF, Pathanamthitta, Kayakulam.**

SCOPE: The scope of work in this tender includes following:

- 1) Supply and Installation of 8MM Thick calcium silicate board of RAMCO make snap grid false ceiling system at 7Nos of LPTV Stations as per following specification:
  - a) Supply, fabrication and erection of snap grid false Ceiling system with GI metallic grids powder coated on its face side. The grid along the wall should be hoisted on wall angles of size 20X20mm fixed to the periphery of the wall at an appropriate height by means of nylon sleeves and wood screws. The main runner of size 24X32mm shall be placed over wall angles at every 1200mm interval horizontally. The main Tees are to be connected with main cross tee angles of size 24X24mm-1200mm long transversally. The main Cross tees are to be further connected with sub cross tees angles of size 24X24-600mm thus forming a grid pattern of 600X600mm center to center. The grids so formed has to be duly suspended to a true level of height and supported by means of 6mm thick down rods drawn from RCC with 6mm self expansion anchor fasteners fixed to all the main runners running at every 1200mm at even interval not exceeding 1350mm. The grids are covered by placing 8MM thick (pre approved) Ramco make Calcium silicate ceiling tiles ,factory finished of size .
  - b) Fixing of departmentally supplied 600x600 lighting systems in the false ceiling.