

PRASAR BHARATI (INDIA'S PUBLIC SERVICE BROADCASTER) Assistant Engineer (Elect.) CIVIL CONSTRUCTION WING ALL INDIA RADIO

प्रसार भारती (गारत के सार्वजनिक सेवा प्रसारक) सहायक अभियंता (विद्युत) सिविल निर्माण विभाग आकाशवाणी

Telephone: 020-25651366Email: aeepune@rediffmail.com# 1085, Old Mehta Bungalow, Ganesh Khind Road, Shivajinagar, Pune - 411 016 #

No-PES/14/Award/2024-25/22

Dated: 17/05/2024

To, M/s Voltas Limited. Domestic Projects Group., Next to Balaji showroom Wakdewadi, 14, Mumbai-Pune road, Pune -411003

<u>Name of work</u>	ARMO Electricals works at NFDC-NFAI PUNE for 2023-24 (Phase-II).				
Sub head:	Replacing of Dehumidifier Coil for 8A and Vault Coil for 5A at Color Film Vault Phase-II.				
<u>Ref: -</u>	 This office letter of acceptance of tender of even no. PES/14/PG/2024- 25/15 dated: 06/05/2024 Performance guarantee letter submitted in Sub - Division Office dated: 17/05/2024, along with FDR No 42974058417 DT: 16/05/2024 issued by STATE BANK OF INDIA for Rs. 19,348 =00 				

Sir,

- 1. In continuation to the letters referred above, you are requested to attend this office to complete formal agreement within seven days from stipulated date of start.
- 2. You are requested to contact the Assistant Engineer (E) CCW, AIR, PUNE for taking possession of the site & to start the work.

Yours faithfully,

ASSISTANT ENGINEER (E)

CCW: AIR: PUNE – 16

Copy to:

- The Executive Engineer (E), CCW, AIR, Mumbai for kind information along with FDR No: 42974058417 DT: 16/05/2024 issued by STATE BANK OF INDIA for Rs. 19,348 =00 as received from M/s VOLTAS LTD. PUNE is enclosed herewith.
- 2. The Manager NFDC-NFAI, Law College Road, Pune.
 - 3. Assistant Engineer (E) CCW AIR / NFAI / FTII-I/II, Pune.
 - 4. Labour officer.
 - 5. Income Tax Officer.
 - 6. Divisional Account.
 - 7. For Agreement.

VEER (E) CCW: AIR: PUNE – 16.

CAL	AKASHVANI, PRASAR B	HARATI			_
Caracter	Schedule of Bi				
Marrie	NIT No: 03/EDM/PUNE/	2024-25			
Nam	e of work:- ARMO Electricals works at NFDC-NFAI PUNE for 2023-24 (Phase-II). (5A at Color Film Vault P	Sub Head :- Ren	lacing of Debund	()	
	5A at Color Film Vault P	ase-II)	nacing of Denumidi	tier Coil for 8A ar	nd Vault Coil fo
Sr.No	INAME OF THE CONTRACTOR/FIRM	Voltas Ltd			
1.0	Description of Item	Quantity			
	Supplying installation testing and commissioning of evaporator coil for Dehumidifier units having Co		0111	Rate	Amount
	face area 600 mm x 600 mm, 12rows deep, Copper Tube Outside dia $5/8"$ (tube thickness 0.50mm), Fin Spacing 4 FPI, with defrost heaters 1 KW 3 Nos, the coil tube sheets shall be of 11 SWG SS304, the entire coil shall be duly coated with superhydrophobic anticorrosive solution including Supplying and fixing of 1no base cum drain tray for evaporating coil of De-Humidifie units made of SS-304, of 2 mm thick with appx size 920mm X 560mm X 100mm etc as required (Dehumidifier Unit 8A)	s. 3	Nos	2,37,938.00	2,37,938.00
2.0	Supplying, Installation, Testing & commissioning of evaporator coil for Vault units having Coil size of $333/4^m \times 251/2^m \times 4$ row deep $\times 1/2^m \times 2000$ cooling coil OD $1/2^m$ copper pipe 24 gauge, 0.15 mm aluminium fins 8 FPI, 16 gauge hard copper pipe 1 1/8" header, 10 way $\times 7/8$ brass distributor with $1/4^m$ copper pipe, anticorrosive color coating 16 gauge SS 304 side plate, ss plate for hanging the coil, including drain tray for evaporating coil of Vault units made of SS-304, of 2 mm thick with appx size 1050mm X 230mm X 75mm etc as required in complete. (Vault Unit 5A)		Nos	1,03,740.00	1,03,740.00
.0	Supply of R 404a refrigerant Gas		_		
		30	Kgs	1,195.00	35,850.00
	NAME OF THE CONTRACTOR/FIRM			Total	3,77,528.00
Sr.No			Voltas Ltd		
1	Name of Component	Estimated cost (in Rs)	Above or Below or at Par	% In Figures	Total Cost
	2	4	5	6	7
1	ARMO Electricals works at NFDC-NFAI PUNE for 2023-24 (Phase-II). (Sub Head :- Replacing of Dehumidifier Coil for 8A and Vault Coil for 5A at Color Film Vault Phase-II)	₹ 3,77,528.00	ABOVE	2.50	3,86,966.00
	Total Amount		2 Land Jack	いたため、キーセロ	
					3,86,966.00

Assistant Engineer (Elect)

.