



P R A S A R B H A R A T I
(INDIA'S PUBLIC SERVICE BROADCASTER)
CIVIL CONSTRUCTION WING, ALL INDIA RADIO
MUMBAI-91

No. AEC-I/BOV/12(NIQ)/2024-25/ 90

Dated: 26.09.2024

NOTICE INVITING QUOTATION

Sealed item rate quotations are invited by The Assistant Engineer (Civil)-I, CCW, AIR, Borivali, Mumbai-91 from the eligible and approved contractors of C.P.W.D. and those on appropriate list of B.S.N.L./M.T.N.L., M.E.S., State P.W.D. of Maharashtra and railways as well as eligible working contractor of CCW AIR for the following work, upto **15.00 hrs.** On 01.10.2024 which shall be opened on the same day at **15.30 Hrs.**


Blank quotation duly signed by Assistant Engineer shall be issued to the agency on submission of application with definite proof of having executed civil work and GST registration no. and acknowledgement of upto date GSTR 1 returns. The blank quotation verified and issued by Assistant Engineer shall only be validated and accepted authority.

Name of work : Annual repair and maintenance operation of office, transmitter and staff quarters building during the year 2024-25 of HPT Akashvani Malad, Mumbai-95.
SH: Civil repairs at security cabin, qtr III/10, II/17, III/16, III/3, II/8, Gate valve repair of main water supply line etc.

Sr. No	Description	Qty.	Unit	Rate	Amount
----- AS PER ATTACHED SHEET -----					
TOTAL:					

CONDITIONS:

1. The work shall be carried out as per CPWD Specifications, 2009 Vol. I & II with upto-date correction slips and as per direction of Engineer-in-charge;
2. Time limit for completion of work is fifteen days.
3. Quoted rates shall be inclusive of all taxes and levies payable under the respective states including GST, nothing extra will be paid on any account;
4. The agency shall visit the site of work before quoting, as no extra payment will be made on any account. Such as extra thickness of base course depths and all height of buildings etc.
5. All type of security measures / precautions of labour shall be responsibility of agency during execution of work. No extra payment will be made on any account.
6. If the work is prolonged beyond stipulated time the penalty shall be imposed @ week.
7. The agency will be responsible for any defect for a period of 12 (twelve) months after issuing completion certificate for the work by Engineer-in-charge & client department. If any defect found during the defect liability period, the agency shall rectify the same within 7 days after receiving the notice from Engineer-in-charge in any form failing which the defective work shall be got rectified / replaced completely at the risk & cost of the agency and no claim whatsoever shall be entertained in this regards. The agency may note that the recovery shall be made from any of the payments due with the department or will be under legal obligation to refund the cost incurred by department in rectification / replacement of the defective work come to the notice of Engineer-in-charge during defect liability period;
8. No advance payment shall be made;
9. Labour should be above 18 years of age.


(M.G. Kurhe)

ASSISTANT ENGINEER (CIVIL)-I
CCW AIR PB (IPSB) MUMBAI-91

CONTRACTOR

Copy to:

1. The Executive Engineer (Civil), Civil Construction Wing, All India Radio, Mumbai-20;
2. The Assistant Engineer Civil (P), CCW, AIR, Mumbai.
3. Notice Board
4. Contractors M/s. _____

SCHEDULE OF WORK

Division Mumbai

Sub-Division Mumbai-1

State

Maharashtra

Branch

Civil

Name of Work :

Annual repair and maintenance operation of office, transmitter and staff quarters building during the year 2024-25 of HPT Akashavani Malad, Mumbai-95.
SH: Civil repairs at security cabin, qtr III/10, IV/17, III/16, III/3, IV/8, Gate valve repair of main water supply line etc.

ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
1	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre-moulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, fascias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels.					
1.1	Granite stone slab of colour black, Cherry/Ruby red					
1.1.1	Area of slab upto 0.50 sqm	0.5	sqm			
2	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.					
2.1	Fixed to openings / wooden frames with rawl plugs screws etc.	70	kg			
3	Providing and fixing bright finished brass 100 mm mortice latch and lock, ISI marked, with six levers and a pair of anodised (anodic coating not less than grade AC 10 as per IS : 1868) aluminium lever handles of approved quality with necessary screws etc. complete.	2	each			
4	Applying priming coat:					
4.1	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	10	sqm			
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :					
5.1	Two or more coats on new work	10	sqm			

ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
6	Cleaning of checked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm dia upto 300mm	4	metre			
7	Providing and fixing solid plastic seat with lid for pedestal type W.C.pan complete :					
7.1	White solid plastic seat with lid	1	each			
8	Providing and fixing panelled door shutter made of anodised aluminium hollow pipe section of size 70 x22 mm for vertical style and horizontal (top/bottom/lock) rails including panelling of 4 mm thick aluminium composite panel sheet and cost of rubber/neoprene gasket required etc complete as per direction of Engineer-in-charge.	2.9	sqm			
9	Repairing 15 mm C.P.brass bibcock/pillar tap/ stop cock by replacing brass spindle of standard size and approved quality etc complete as per direction of Engineer-in-charge.	5	each			
10	Removing the existing wooden door shutter ,cutting the edges and re-fixing the same of all size of door etc. as per direction of Engineer in charge.	1	each job			
11	Rendering services of skilled labour i.e. plumber for repairing leaked water supply line, repairing accessories etc at required location etc as per direction of Engineer-in-Charge	3	each			
12	Repairing existing wooden glazed window shutters including removing and replacing damaged wooden member of shutter; repairing remaining part by jack plane , removing and re-fixing existing grill work including nails, screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	2	each			
13	Supplying and fixing at site 15mm C.P brass angle push cock tap of approved quality and conforming to I.S standards etc complete as per direction of Engineer-in-charge.	1	each			
	Total					